

04-16-01

09/807654CT #
Express Mail Label No. EL623519943US

04/13/01

PTO-1390
(1-2000)
U.S. PTO

U.S. DEPARTMENT OF COMMERCE PATENT AND TRADEMARK OFFICE

ATTORNEY'S DOCKET NUMBER

TRANSMITTAL LETTER TO THE UNITED STATES
DESIGNATED/ELECTED OFFICE (DO/EO/US).
CONCERNING A FILING UNDER 35 U.S.C. 371

5077-000031

U.S. APPLICATION NO. (If known, see 37 CFR 1.5)

INTERNATIONAL APPLICATION NO.

INTERNATIONAL FILING DATE

PRIORITY DATE CLAIMED

PCT/JP00/02474

17 April 2000 (17.04.00)

16 April 1999 (16.04.99)

TITLE OF INVENTION IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM

APPLICANT(S) FOR DO/EO/US OKAMOTO, Shusaku; NAKAGAWA, Masamichi; NOBORI, Kunio and
MORIMURA, Atsushi

Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:

1. ☒ This is a **FIRST** submission of items concerning a filing under 35 U.S.C. 371.
2. ☐ This is a **SECOND** or **SUBSEQUENT** submission of items concerning a filing under 35 U.S.C. 371.
3. ☒ This is an express request to begin national examination procedures (35 U.S.C. 371(f)). The submission must include items (5), (6), (9) and (21) indicated below.
4. ☐ The US has been elected by the expiration of 19 months from the priority date (Article 31).
5. ☒ A copy of the International Application as filed (35 U.S.C. 371(c)(2))
 - a. ☐ is attached hereto (required only if not communicated by the International Bureau).
 - b. ☒ has been communicated by the International Bureau.
 - c. ☐ is not required, as the application was filed in the United States Receiving Office (RO/US).
6. ☒ An English language translation of the International Application as filed (35 U.S.C. 371(c)(2)).
 - a. ☒ is attached hereto.
 - b. ☐ has been previously submitted under 35 U.S.C. 154(d)(4).
7. ☒ Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371(c)(3))
 - a. ☐ are attached hereto (required only if not communicated by the International Bureau).
 - b. ☐ have been communicated by the International Bureau.
 - c. ☐ have not been made; however, the time limit for making such amendments has NOT expired.
 - d. ☒ have not been made and will not be made.
8. ☐ An English language translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371 (c)(3)).
9. ☒ An oath or declaration of the inventor(s) (35 U.S.C. 371(c)(4)).
10. ☐ An English language translation of the annexes of the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371(c)(5)).

Items 11 to 20 below concern document(s) or information included:

11. ☒ An Information Disclosure Statement under 37 CFR 1.97 and 1.98.
12. ☒ An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included.
13. ☐ A **FIRST** preliminary amendment.
14. ☐ A **SECOND** or **SUBSEQUENT** preliminary amendment.
15. ☐ A substitute specification.
16. ☐ A change of power of attorney and/or address letter.
17. ☐ A computer-readable form of the sequence listing in accordance with PCT Rule 13ter.2 and 35 U.S.C. 1.821 - 1.825.
18. ☐ A second copy of the published international application under 35 U.S.C. 154(d)(4).
19. ☐ A second copy of the English language translation of the international application under 35 U.S.C. 154(d)(4).
20. ☒ Other items or information:

47 sheets of drawing showing FIGS. 1-50, copy of English Translation of International Search Report, Form PTO-1449 and copies of the references cited therein (2 JP), and return receipt postcard

U.S. APPLICATION NO. (If known) Fee 37 CFR 1.101

09/807654

INTERNATIONAL APPLICATION NO
PCT/JP00/02474ATTORNEY'S DOCKET NUMBER
5077-00003121. ☒ The following fees are submitted:**BASIC NATIONAL FEE (37 CFR 1.492 (a) (1) - (5)):**Neither international preliminary examination fee (37 CFR 1.482)
nor international search fee (37 CFR 1.445(a)(2)) paid to USPTO
and International Search Report not prepared by the EPO or JPO \$1000.00International preliminary examination fee (37 CFR 1.482) not paid to
USPTO but International Search Report prepared by the EPO or JPO \$860.00International preliminary examination fee (37 CFR 1.482) not paid to USPTO
but international search fee (37 CFR 1.445(a)(2)) paid to USPTO \$710.00International preliminary examination fee (37 CFR 1.482) paid to USPTO
but all claims did not satisfy provisions of PCT Article 33(1)-(4) \$690.00International preliminary examination fee (37 CFR 1.482) paid to USPTO
and all claims satisfied provisions of PCT Article 33(1)-(4) \$100.00**ENTER APPROPRIATE BASIC FEE AMOUNT =**

CALCULATIONS PTO USE ONLY

\$ 860.00

Surcharge of \$130.00 for furnishing the oath or declaration later than ☐ 20 ☐ 30
months from the earliest claimed priority date (37 CFR 1.492(e)).

\$ 0.00

CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE
Total claims	29 -20 =	9	x \$18.00
Independent claims	10 -3 =	7	x \$80.00
MULTIPLE DEPENDENT CLAIM(S) (if applicable)			+ \$270.00
TOTAL OF ABOVE CALCULATIONS =			\$ 1,852.00

\$

Total claims 29 -20 = 9 x \$18.00 \$ 162.00

\$ 162.00

Independent claims 10 -3 = 7 x \$80.00 \$ 560.00

\$ 560.00

MULTIPLE DEPENDENT CLAIM(S) (if applicable) + \$270.00 \$ 270.00

\$ 270.00

TOTAL OF ABOVE CALCULATIONS = \$ 1,852.00

\$ 1,852.00

☐ Applicant claims small entity status. See 37 CFR 1.27. The fees indicated above
are reduced by 1/2. + \$ 0.00

\$ 0.00

SUBTOTAL =

\$ 1,852.00

Processing fee of \$130.00 for furnishing the English translation later than ☐ 20 ☐ 30
months from the earliest claimed priority date (37 CFR 1.492(f)).

\$ 0.00

TOTAL NATIONAL FEE =

\$ 1,852.00

Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be
accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31). \$40.00 per property +

\$ 40.00

TOTAL FEES ENCLOSED =

\$ 1,892.00

Amount to be
refunded: \$

charged: \$

a. ☒ A check in the amount of \$ 1,892.00 to cover the above fees is enclosed.b. ☐ Please charge my Deposit Account No. _____ in the amount of \$ _____ to cover the above fees.
A duplicate copy of this sheet is enclosed.c. ☒ The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any
overpayment to Deposit Account No. 08-0750. A duplicate copy of this sheet is enclosed.d. ☐ Fees are to be charged to a credit card. **WARNING:** Information on this form may become public. **Credit card
information should not be included on this form.** Provide credit card information and authorization on PTO-2038.**NOTE:** Where an appropriate time limit under 37 CFR 1.494 or 1.495 has not been met, a petition to revive (37 CFR
1.137 (a) or (b)) must be filed and granted to restore the application to pending status.

SEND ALL CORRESPONDENCE TO:

Gregory A. Stobbs
Harness, Dickey & Pierce, P.L.C.
P. O. Box 828
Bloomfield Hills, MI 48303
US

SIGNATURE

Gregory A. Stobbs

NAME

28,764

REGISTRATION NUMBER

Date: April 13, 2001

(51) 国際特許分類

H04N 7/18, B60R 1/00, G03B 15/00,
37/00

A1

(11) 国際公開番号

WO00/64175

(43) 国際公開日

2000年10月26日(26.10.00)

(21) 国際出願番号

PCT/JP00/02474

(22) 国際出願日

2000年4月17日(17.04.00)

(30) 優先権データ

特願平11/109946

1999年4月16日(16.04.99)

JP

(71) 出願人 (米国を除くすべての指定国について)

松下電器産業株式会社

(MATSUMITA ELECTRIC INDUSTRIAL CO., LTD.)

[JP/JP]

〒571-8501 大阪府門真市大字門真1006番地 Osaka, (JP)

(72) 発明者; および

(75) 発明者/出願人 (米国についてのみ)

岡本修作(OKAMOTO, Shusaku)[JP/JP]

〒573-0013 大阪府枚方市星丘3-6-10-215 Osaka, (JP)

中川雅通(NAKAGAWA, Masamichi)[JP/JP]

〒573-0151 大阪府枚方市藤阪北町22-5-304 Osaka, (JP)

登 一生(NOBORI, Kunio)[JP/JP]

〒571-0063 大阪府門真市常称寺町16-1-811 Osaka, (JP)

森村 淳(MORIMURA, Atsushi)[JP/JP]

〒631-0006 奈良県奈良市西登美ヶ丘4-14-8 Nara, (JP)

(74) 代理人

前田 弘, 外(MAEDA, Hiroshi et al.)

〒550-0004 大阪府大阪市西区靱本町1丁目4番8号

太平ビル Osaka, (JP)

(81) 指定国 CA, CN, JP, KR, US, 欧州特許 (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE)

添付公開書類


国際調査報告書

(54) Title: IMAGE PROCESSING DEVICE AND MONITORING SYSTEM

(54) 発明の名称 画像処理装置および監視システム

(57) Abstract

A synthetic image viewed from a virtual viewpoint above a car is created from images captured by cameras for imaging the surroundings of the car. In the synthetic image, an illustrated or real image of the car is displayed in the area where the car is present. The area which is not imaged by any of the cameras is displayed as a blind spot.



C...IMAGE BY CAMERA 3 H...X COORDINATE
D...IMAGE BY CAMERA 2 I...Y COORDINATE
E...IMAGE BY CAMERA 6 J...DEGREE OF NECESSITY
G...CAMERA NO. L...IMAGE BY CAMERA 1

M...CORRESPONDENCE BETWEEN MAPPING TABLE AND SYNTHETIC IMAGE

47/8211

09/807654

JCOB Rec'd TGT/PAD 13 APR 2001

DESCRIPTION

IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM

5 Technical Field

The present invention relates to an image processing technique for generating synthetic images with images captured by a plurality of cameras. In particular, the present invention relates to an effective technique for a
10 monitoring system that can be utilized as an aid to confirm safety when driving a vehicle.

Background Art

In conventional monitoring systems in general, one or a
15 plurality of monitoring cameras capture an image of an object to be monitored, and the image is displayed on a monitor. In this case, generally, monitors are prepared in the number corresponding to the number of the cameras installed for monitoring.

20 For example, a conventional safety monitoring system for vehicles is as follows. A camera for capturing images is installed around the vehicle, and the images captured by the camera are displayed on a monitor installed near the driving seat. This system allows the driver to confirm safety of
25 places of which safety confirmation is difficult with eyes or a mirror, such as an area behind the vehicle, through the monitor.

Japanese Patent Publication No. 2696516 discloses a structure that displays images on a divided monitoring screen, depending on the gear or the car speed. More specifically, when it is determined that the vehicle is in the halt state or in the low speed state, the monitoring screen is divided into three sections, and images captured by three cameras installed on the right side, the left side and in a lower portion of the vehicle are synthesized and reproduced. When it is determined that the vehicle is in the forward running state, the monitoring screen is divided into two sections, and images captured by two cameras installed on the right side and the left side of the vehicle are synthesized and reproduced.

Japanese Laid-Open Patent Publication No. 11-78692 discloses a video presenting apparatus for vehicles having a structure in which precise videos for each encountered scene are synthesized and displayed. More specifically, camera images are transformed and synthesized depending on the driving state of the vehicle such as backward parking, forward parking, parallel parking or a state where the vehicle goes into an intersection with an obstructed view.

However, such conventional structures are not necessarily convenient systems for users such as drivers of vehicles.

Disclosure of Invention

It is an object of the present invention to provide an

improved image processing apparatus or an improved monitoring system in the convenience of users such as drivers of vehicles.

More specifically, an image processing apparatus of the present invention includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image viewed from a virtual point of view from these camera images, wherein the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view in accordance with a running state of the vehicle.

It is preferable that the image processing part changes at least one selected from the position of the virtual point of view, the direction of the line of sight, and the focal length in accordance with a running speed of the vehicle.

It is preferable that the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view, and controls capturing of an image outside a view range of the changed virtual point of view.

It is preferable that the image processing part controls the capturing of an image outside a view range of the changed virtual point of view by changing a model for image synthesis.

It is preferable that the image processing part changes at least one selected from the position, the direction of the

line of sight, and the focal length of the virtual point of view in accordance with a steering angle of the vehicle.

It is preferable that the image processing part changes at least one selected from the position, the direction of the
5 line of sight, and the focal length of the virtual point of view in accordance with results of detection by an object detecting sensor that is provided in the vehicle.

It is preferable that the image processing part includes an original mapping table and generates a synthetic
10 image using a mapping table that is cut out from the original mapping table, and the image processing part changes at least one selected from the position, the direction of the line of sight, and the focal length of the virtual point of view by changing the mapping table to be cut out from the original
15 mapping table.

According to another aspect of the present invention, an image processing apparatus includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic
20 image viewed from a virtual point of view from these camera images, wherein the image processing part controls capturing of an image outside a view range of the virtual point of view in accordance with a running state of the vehicle.

According to another aspect of the present invention, a
25 monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to

generate a synthetic image viewed from a virtual point of view from these camera images; and a display part for displaying the synthetic image, wherein the image processing part changes at least one selected from the position, the
5 direction of the line of sight, and the focal length of the virtual point of view in accordance with a running state of the vehicle.

More specifically, an image processing apparatus of the present invention includes an image processing part for
10 receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part generates an image including a first image and a second image as the synthetic image, the first image being viewed from a
15 virtual point of view, the second image being viewed from a viewpoint that is different from the virtual point of view of the first image in at least one selected from the position, the direction of the line of sight and the focal length, or the second image being different from the first image in the
20 model.

It is preferable that the second image is at least one of the camera images.

It is preferable that the first image is a close view image showing the vehicle and surroundings thereof, and the
25 second image is a distant view image showing an area distant from the surrounding area of the vehicle that is shown by the close view image. It is preferable that the image processing

part arranges the distant view image around the close view image in the synthetic image. It is preferable that the distant view image is an image having continuity with the close view image.

5 It is preferable that the first image shows at least a part of the vehicle and at least a part of the surroundings of the vehicle, and the second image is obtained by enlarging at least a part of the area shown by the first image.

 According to another aspect of the present invention, a
10 monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to generate a synthetic image from these camera images; and a display part for displaying the synthetic image, wherein the
15 image processing part generates an image including a first image and a second image as the synthetic image, the first image being viewed from a virtual point of view, the second image being viewed from a viewpoint that is different from the virtual point of view of the first image in at least one
20 selected from the position, the direction of the line of sight and the focal length, or the second image being different from the first image in the model.

 More specifically, an image processing apparatus of the present invention includes an image processing part for
25 receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein in the synthetic image, the

image processing part displays at least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

5 It is preferable that the synthetic image is an image viewed from a virtual point of view that is set above the vehicle.

 It is preferable that the image processing part displays an illustration image or an actual image of the
10 vehicle on the vehicle region.

 It is preferable that the attention drawing region includes at least a part of a blind spot region around the vehicle that is not shot by any of the cameras. Alternatively, it is preferable that the attention drawing
15 region corresponds to the blind spot region around the vehicle that is not shot by any of the cameras. It is preferable that the image processing part determines a range of a region obtained by combining the blind spot region and the vehicle region, using region data showing a projection
20 region of the vehicle in each camera image.

 According to another aspect of the present invention, a monitoring system includes a plurality of cameras shooting surroundings of a vehicle; an image processing part for receiving images captured by the plurality of cameras to
25 generate a synthetic image from these camera images; and a display part for displaying the synthetic image, wherein in the synthetic image, the image processing part displays at

least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

5 More specifically, an image processing apparatus of the present invention includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part
10 generates the synthetic image, using a mapping table including first mapping data describing a correspondence relationship between pixels of the synthetic image and pixels of the camera images, and second mapping data describing an identifier showing that a pixel of the synthetic image
15 corresponds to pixel data other than the camera images.

It is preferable that the pixel data other than the camera images shows the vehicle or a blind spot region that is present in at least a part of the surroundings of the vehicle.

20 It is preferable that the image processing part stores a predetermined image other than the camera images, and with respect to the pixel of the synthetic image, the second mapping data describes coordinate values in the stored predetermined image corresponding to the pixel.

25 It is preferable that the second mapping data describes pixel data corresponding to the pixel of the synthetic image.

According to another aspect of the present invention,

an image processing apparatus includes an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing
5 part uses mapping data describing a correspondence relationship between pixels of the synthetic image and a plurality of pixel data including one or both of pixel data of the camera images and pixel data other than the camera images, and describing the rate of necessity with respect to
10 each of the pixel data, and weights each pixel data in accordance with the rate of necessity, thereby generating the pixel data of the pixels of the synthetic image.

According to another aspect of the present invention, an image processing apparatus includes an image processing
15 part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images, wherein the image processing part includes an original mapping table, cuts out a mapping table describing a correspondence relationship between pixels
20 of the synthetic image and pixels of the camera images, and generates the synthetic image, using the cut-out mapping table.

Brief Description of Drawings

25 Fig. 1 is a conceptual diagram of a monitoring system of the present invention.

Figs. 2(a) and 2(b) are views showing an example of

camera arrangement.

Fig. 3 is an example of images captured by the cameras of Figs. 2(a) and 2(b).

Fig. 4 is a view conceptually showing the relationship
5 between a virtual point of view and actual cameras.

Fig. 5 is an example of a generated synthetic image.

Figs 6(a) to 6(e) are views showing an image synthesis operation using a mapping table.

Fig. 7 is an example of a structure of a monitoring
10 system of an embodiment of the present invention.

Fig. 8 is a flowchart showing an operation of an image synthesis part of Fig. 7.

Fig. 9 is an example of a structure of a mapping table.

Fig. 10 is a flowchart showing the detail of the pixel
15 synthesis step S14 of Fig. 8.

Fig. 11 is an example of mapping data that describe pixel data other than the camera images.

Fig. 12 is an example of a vertically downward view image utilizing images from eight cameras.

Fig. 13 is an example of a vertically downward view
20 image utilizing images from four cameras.

Fig. 14 is an example of a vertically downward view image utilizing images from two cameras.

Fig. 15 is an example of an obliquely downward view
25 image.

Fig. 16 is an example of a panorama image in forward panorama mode.

Fig. 17 is an example of a panorama image in backward panorama mode.

Fig. 18 is an example of a combination of an obliquely downward view image and a panorama image.

5 Figs. 19(a) to 19(f) show an example of synthetic images when the height of the virtual point of view is changed in accordance with the running state of the vehicle.

10 Figs. 20(a) to 20(d) show an example of synthetic images when the direction of the line of sight of the virtual point of view is changed in accordance with the running state of the vehicle.

15 Figs. 21(a) and 21(b) show an example of synthetic images when the direction of the line of sight of the virtual point of view is changed in accordance with the steering angle of the vehicle.

Figs. 22(a) and 22(b) are views showing an example of image switching in accordance with output signals from an object detecting sensor.

20 Fig. 23 is a view showing an example of image switching in accordance with output signals of an object detecting sensor.

Fig. 24 shows views showing an example of image switching in accordance with output signals of an object detecting sensor.

25 Fig. 25 is an example of a structure of a monitoring system of an embodiment of the present invention.

Figs. 26(a) to 26(d) are views showing cutting-out of a

mapping table for parallel displacement of an image.

Figs. 27(a) to 27(g) are views showing cutting-out of a mapping table for enlargement or contraction of an image.

Fig. 28 is a view showing cutting-out of a mapping
5 table in the shape of a quadrangle other than a square.

Fig. 29 is an example of camera images.

Fig. 30 is an example of a synthetic image where camera images showing an obliquely backward view is attached on the right and the left of a downward view image.

10 Fig. 31 is an example displaying a downward view image in a narrow range and a downward view image in a wide range side by side.

Fig. 32 is an example where obliquely downward view images are attached around the downward view image.

15 Fig. 33 is an example where an image utilizing a quasi-cylindrical model is attached around the downward view image.

Fig. 34 is an example where panorama images are attached around the downward view image.

20 Fig. 35 is an example where obliquely downward view images are attached around the downward view image with blank portions at the four corners.

Fig. 36 is an example displaying an image showing the position of a virtual point of view together with a camera image.

25 Fig. 37 shows views showing an example of camera images and mask data showing projection regions of the vehicle.

Figs. 38(a) to 38(c) are views showing an example where

an image of the vehicle is superimposed.

Fig. 39 shows views showing an example of synthetic images when a projection of the vehicle is converted as it is.

Fig. 40 shows views showing a part of the mask data.

5 Fig. 41 is an example of a synthetic image showing a vehicle region and a blind spot region.

Fig. 42 is a diagram showing a procedure for generating mapping data for obtaining the blind spot region and attaching images of a vehicle.

10 Figs. 43(a) to 43(d) are diagrams showing the relationship between the mask data and the pixels of the synthetic images.

Figs 44(a) to 44(c) show an example of synthetic images when mapping data obtained as a result of the procedure of
15 Fig. 42 are used.

Fig. 45 is a diagram showing a procedure for generating mapping data for designating an attention drawing region.

Figs. 46(a) to 46(c) show an example of synthetic images when mapping data obtained as a result of the
20 procedure of Fig. 45 are used.

Fig. 47 is a diagram for illustrating geometric transformation.

Fig. 48 is a diagram for illustrating geometric transformation.

25 Fig. 49 is a diagram for illustrating geometric transformation.

Fig. 50 is a diagram for illustrating geometric

transformation.

Best Mode for Carrying Out the Invention

Fig. 1 is a conceptual diagram of a monitoring system
5 of the present invention. In the monitoring system of Fig. 1,
an image processing part 2 receives a plurality of camera
images output from an image capturing part 1, and synthesizes
the images to generate a synthesis image viewed from a
virtual point of view. This synthetic image is displayed by
10 a displaying part 3 such as a liquid crystal display. The
image processing part 2 constitutes an image processing
apparatus of the present invention.

In the description herein, a monitoring system of the
present invention is mounted on a vehicle to assist parking
15 or the like.

Figs. 2(a) and 2(b) show an example of camera
arrangement. Fig. 3 is an example of images captured by the
cameras arranged in Figs. 2(a) and 2(b). As shown in Figs.
2(a) to 2(b), five cameras are provided in the vicinity of
20 the door mirror, in the vicinity of the rear pillar and on
the rear trunk. The image processing part 2 generates a
synthetic image from five camera images when viewed from a
virtual point of view.

The virtual point of view can be set to be oriented to
25 an arbitrary direction in an arbitrary position in a three-
dimensional space as in the case of a camera arrangement in
video generation of computer graphics. The parameters that

determine the virtual point of view are coordinates (X-axis, Y-axis, Z-axis) representing the position of the virtual point of view in a three-dimensional space, three angles representing the direction, namely, an azimuth (horizontal rotation), an elevation angle (gradient) and a twist (rotation about the optical axis), and a focal length defining the view range. The focal length is a distance between the virtual point of view and a projection plane on which a synthetic image is generated. When the focal length is small, an image with a wide angle is generated. When the focal length is large, a telescopic image is generated. In actual cameras, the focal length is often represented by a distance (mm) with respect to the size (35mm) of a film that is the projection plane. In this specification, since the size of a synthetic image is represented by pixels, the focal length is also represented by pixels.

An appropriate synthetic image can be generated by selecting the position, the direction and the focal length of the virtual point of view depending on the situation.

Fig. 4 is a view conceptually showing the relationship between a virtual point of view and actual cameras. In Fig. 4, the virtual point of view is set above the vehicle. Fig. 5 is an example of a generated synthetic image, which is an image showing the vehicle and the scene around the vehicle viewed from the virtual point of view shown in Fig. 4.

In this embodiment, the image processing part 2 uses a mapping table 4 to generate a synthetic image from a

plurality of camera images. Herein, a "mapping table" refers to a table that describes the correspondence relationship between pixels for a synthetic image and pixel data of each camera image. As described later, in the mapping table, a
5 correspondence relationship between pixels for a synthetic image and pixel data other than the camera images can be described.

Principle of the mapping table

10 Hereinafter, an operation for generating a synthetic image from a plurality of camera images using the mapping table will be described.

Figs. 6(a) to 6(e) are views for illustrating the outline of this operation. Figs. 6(a) to 6(c) are images
15 captured by three cameras (corresponding to camera 3, camera 1 and camera 2 in Fig 2(a), respectively. Fig. 6(d) is a mapping table used for generating a synthetic image from the camera images of Figs. 6(a) to 6(c). The image processing
part 2 generates a synthetic image shown in Fig. 6(e) from
20 the three camera images of Figs. 6(a) to 6(c), based on information of the mapping table of Fig. 6(d).

The mapping table shown in Fig. 6(d) has mapping data about each pixel of the synthetic image shown in Fig. 6(e). Each mapping datum describes information about a pixel of a
25 camera image by which the corresponding pixel of the synthetic image is generated.

"Generating a synthetic image" means to determine

values of all the pixels of the synthetic image. Herein, the image processing part 2 determines values of pixels of the synthetic images in the order of the raster sequentially from the upper left, and the operation will be described by taking
5 an example of the case of determining a value of a pixel P1 in the middle of the raster.

First, mapping data MP1 corresponding to the pixel P1 of the synthetic image is referred to. In the mapping data MP1, the corresponding camera number and the coordinates of
10 the corresponding pixel of the camera image. In this example, in the mapping data MP1, "1" is described as the camera number and "340" as the X coordinate and "121" as the Y coordinate are described.

The image processing part 2 refers to pixel data C1 of
15 the coordinates (340, 121) of the image captured by the camera 1 shown in Fig. 6(b), according to the description of the mapping data MP1 so as to determine the value of the pixel P1 of a synthetic image. Herein, the simplest method for determination is to use the value C1 of the pixel data as
20 the value of the pixel P1. The synthetic image as shown in Fig. 6(e) is generated by determining the value of each pixel of the synthetic image by the same method.

For example, the mapping data MP2 corresponding to the pixel P2 of the synthetic image shows the pixel data C2 of
25 the image captured by the camera 2 shown in Fig. 6(c), and therefore the value of the pixel data C2 is assigned as the value of the pixel P2. Similarly, the mapping data MP3

corresponding to the pixel P3 of the synthetic image shows the pixel data C3 of the image captured by the camera 3 shown in Fig. 6(a), and therefore the value of the pixel data C3 is assigned as the value of the pixel P3. In the mapping table
5 of Fig. 6(d), a region R1 corresponds to the camera 1, and a region R2 corresponds to the camera 2, and a region R3 corresponds to the camera 3.

A region R4 other than the three regions R1 to R3 corresponding to the cameras is not covered by the cameras,
10 or a blind spot that is hidden by the vehicle so that no corresponding camera images are present. For example, a pixel P4 of the synthetic image is a pixel of the region R4. In this case, as the camera number of the mapping data MP4 corresponding to the pixel P4, a specific camera number ("-1"
15 in this example) that indicates that there is no corresponding camera image is used. When the camera number is "-1", predetermined pixel data indicating that this is outside the camera coverage or a blind spot are set for the corresponding pixel P4. Herein, black is set as the
20 predetermined pixel data.

In the example of Figs. 6(a) to 6(e), the mapping table is constituted so that a synthetic image overlooking the surroundings of the vehicle from the virtual point of view above the vehicle can be generated. This kind of mapping
25 table can be prepared using geometric transformation that utilizes a so-called road surface plane model as described later. Alternatively, the mapping table can be prepared in

the trial and error manner while watching the synthetic image.

In fact, the correspondence relationship between the synthetic image and the pixel data of the camera images can be set freely depending on the purpose. For example, an arbitrary region of the camera image can be enlarged or contracted to synthesize the region in a part of the camera image, or a plurality of camera images can be aligned and synthesized. Thus, an arbitrary synthetic image can be generated.

For any mapping tables for generating a synthetic image, the image processing part 2 only has to perform the steps of referring to mapping data, referring to the pixel data of the designated camera image, and setting a pixel value of the synthetic image with respect to each pixel of the synthetic image. Therefore, the processing amount thereof can be significantly smaller than in the case where image synthesis is performed by an operation for each image synthesis. Therefore, in this method, the processing amount is constant, regardless of the type of the synthetic image, and high speed processing can be achieved, so that this method is most advantageous when used for monitoring that is required to be completed real-time in a predetermined period of time or for driving aid.

(First example of an operation for generating a synthetic image)

Fig. 7 is a diagram showing an example of a structure

of a monitoring system of this embodiment. In Fig. 7, the image processing part 2 includes an image synthesizing part 200, a display pattern storing part 210 and a display pattern setting part 220. The displaying storing part 210 includes a mapping table storing part 211 for storing a plurality of mapping tables as described above. The display pattern setting part 220 selects one mapping table MPT in accordance with the display pattern of a synthetic image to be generated from the mapping tables stored in the mapping table storing part 211, and sets it to a mapping table reference part 202 of the image synthesizing part 200.

Furthermore, the display pattern storing part 210 includes an illustration storing part 212 for storing various illustration images. The display pattern setting part 220 reads out an illustration image necessary for generation of a synthetic image from the illustration image storing part 212, and sets the illustration image to an illustration reference part 203 of the image synthesizing part 200. Here, the illustration image showing the vehicle is set.

The image synthesizing part 200 generates a synthetic image using a camera image output from the image capturing part 1 in accordance with the mapping table MPT set in the mapping table reference part 202. A timing generating part 205 generates timing signals for generating an animation sequence of the synthetic image.

Each camera 101 is provided with a pair of frame memories 102a and 102b. Each camera 101 is of a CCD type in

this example. When the camera is of a CMOS type, the camera can be provided with a frame memory function. In this case, the frame memories can be omitted.

Fig. 8 is a flowchart showing an operation of the image synthesizing part 200 for generation of one frame of a synthetic image.

First, the image capturing part 1 switches between the frame memory 102a in which images captured by each camera 101 are written and the frame memory 102b referred to by the image synthesizing part 200, in accordance with the timing signal for frame start output from the timing generation part 205 (step S11). The two frame memories are provided in each camera 101 and switched in order to prevent the writing and the reference from interfering with each other, because the image synthesizing part 200 refers to pixel data of the camera image here and there in accordance with the mapping table MPT, regardless of the order of writing from the camera 101, as described later.

Next, the timing generating part 205 generates a timing signal for designating a pixel for synthesis processing to the mapping table reference 202 (step S12). The mapping table reference part 202 reads out mapping data corresponding to the designated pixel from the mapping table MPT and outputs the data to the pixel synthesizing part 201 (step S13).

The pixel synthesizing part 201 generates a value of the pixel of the designated image in accordance with the

content of the input mapping data, using the pixel data of each camera image stored in the frame memory 102, the pixel data of the illustration images stored in the illustration reference part 203 and the like, and outputs the value to a video signal generating part 204 (step S14). The processing of step S14 will be described later.

The video signal generating part 204 converts the input pixel value of the synthetic image to a video signal in accordance with the timing signal output from the timing generating part 205, and outputs the video signal to a displaying part 3 (step S15).

The image synthesizing part 200 executes the processing of steps S12 to S15 with respect to all the pixels of the frame (steps S16, S17). When processing for the final pixel of the frame is completed, the timing generating part 205 starts the processing for the next frame.

The same processing can be executed by field unit.

Fig. 9 is a diagram showing an example of the structure of the mapping table. The mapping table shown in Fig. 9 has four types of mapping data MP11 to MP14. The structure of each mapping data is basically the same as those shown in Fig. 6, except that the rate of necessity of the pixel value is described, in addition to the camera number and the x, y coordinates. Herein, "the rate of necessity" is represented by values from 0 to 1, and the larger the value is, the higher the necessity is.

The mapping data MP11 describes the correspondence

relationship between the pixel of the synthetic image and the pixel data of one camera image. In this case, the rate of necessity is "1". The mapping data MP12 describes the correspondence relationship between the pixel of the synthetic image and the pixel data of a plurality of camera images. In this case, the pixel data of the camera image are weighted in accordance with the rate of necessity to generate the pixel value of the synthetic image.

The mapping data MP13 is used to attach the pixel data of the illustration image to the pixel of the synthetic image. More specifically, the number that does not correspond to any actual cameras ("99" in this example) is assigned to the illustration reference part 203 as the camera number so that an illustration image stored in the illustration reference part 203 can be identified.

The mapping data MP14 indicates that the pixel of the synthetic image is in a so-called blind spot region. More specifically, when generating the mapping table, as a result of calculating the coordinate values of the pixel of the camera image that is referred to for generation of the pixel of the synthetic image, when the pixel of the coordinate values represent, for example, the vehicle itself, the pixel of the synthetic image fall on a region obtained by combining the vehicle region and the blind spot region. The blind spot region is a region obtained by subtracting the vehicle region from the combined region. For this reason, the blind spot region can be represented by assigning values that do not

exist as the camera numbers or the x, y coordinates. In this example, "-1" is assigned as the camera number.

Fig. 10 is a flowchart showing the flow of the detailed process of the pixel synthesis step S14.

5 First, a value of the pixel for synthesis is initialized to "0" (step S21).

Next, the camera number, the x, y coordinates and the rate of necessity are read out from the mapping data corresponding to the pixel for synthesis (step S22).

10 In step S22, when the camera number that has been read out is an identification number "99" indicating an illustration image (that is, the case of the mapping data MP13), the procedure goes to step S24, where the pixel data of the designated x, y coordinates of the illustration image
15 stored in the illustration reference part 203 are read out and stored. Then, the procedure goes to step S28. On the other hand, when the camera number is not "99", the procedure goes to step S25.

In step S25, when the camera number that has been read
20 out is an identification number "-1" indicating a blind spot region (that is, the case of the mapping data MP14), the procedure goes to step S26, where the pixel data representing the blind spot region that has been previously set are stored. Then, the procedure goes to step S28. On the other hand,
25 when the camera number is not "-1", the procedure goes to step S27.

In step S27, when the camera number is not "99" or "-1",

that is, when it is determined that the pixel for synthesis is not in a region on which an illustration image is attached nor the blind spot region, the camera number represents the number of an actual camera, so that the pixel data of the designated x, y coordinates are read out from the camera images stored in the frame memory 102 of the corresponding camera number.

In step S28, the stored pixel data are weighted in accordance with the rate of necessity and added to the pixel value of the synthetic image. With respect to all the camera numbers described in the mapping data, steps S22 to S28 are repeated (steps S29, S30). When the processing is completed with respect to all the camera numbers, the image synthesizing part 201 outputs the values of the pixels (step S31).

For example, in the case of the mapping data MP12 shown in Fig. 9, the pixel value of the synthetic image can be obtained by the following equation.

$$\begin{aligned} &\text{The pixel value of the synthetic image} = \\ &(\text{the pixel value of the coordinates (10,10) of the} \\ &\text{camera 2} \times 0.3 \\ &+ \text{the pixel value of the coordinates (56,80) of the} \\ &\text{camera 3} \times 0.5) \\ &/ (0.3 + 0.5) \end{aligned}$$

Herein, division by the sum of the degrees of necessity (0.3 + 0.5) is performed to normalize the pixel value.

The above-described operation easily can generate a

synthetic image obtained by combining a plurality of camera images or a synthetic image including an illustration image. Furthermore, a synthetic image obtained by displaying a semi-transparent illustration image on an actual image can be
5 generated by weighting the camera image and the illustration image in accordance with the rate of necessity. Moreover, a synthetic image obtained by displaying semi-transparent illustration images can be generated by weighting the pixel data other than the camera image in accordance with the rate
10 of necessity.

Furthermore, as the illustration image, illustration images other than illustrations or images of the vehicle, such as those having a fixed shape on a screen such as a scale or an index of images, can be used.

15 In the description of this example, the camera number ("99") for referring to the illustration images and the camera number ("-1") for indicating the blind spot region are set independently. However, if the images representing the blind spot region are stored in the illustration reference
20 part 203, the same camera number ("99") can be used for referring to the illustration images and for indicating the blind spot. In this case, for example, it is possible to store the illustration images representing the vehicle in combination with the images representing the blind spot
25 region in the illustration reference part 203.

Furthermore, when the display pattern is changed in response to the designation of the display mode, it is

sufficient for the display pattern setting part 220 to read out a mapping table corresponding to a new display pattern from the mapping table storing part 211, and to set it in the mapping table reference part 202. Alternatively, a plurality
5 of mapping tables may be synthesized so that a new mapping table can be generated.

In this example, as the mapping data MP13 shown in Fig. 9, the X, Y coordinate values of the illustration reference part 203 are described to display the illustration image.
10 However, the pixel data itself of the illustration image can be described in the mapping data instead.

Fig. 11 is an example of the mapping data in this case. In the mapping data MP15 of Fig. 11, when the camera number is "99", that is, an illustration image is displayed, the
15 pixel data itself of the illustration image are stored in the form of the values of red (R), green (G) and blue (B) in the region where the x coordinate and the y coordinate are stored.

For example, if the X coordinate and the Y coordinate are represented with 16 bits, the size of the region is 32
20 bits. On the other hand, if the image data of the illustration image are represented with 8 bits each for R, G and B, the data are constituted with 24 bits in total. 8 bits "0" are added as the upper bits to make it 32 bit data, and the data are stored in the coordinate region. In this
25 case, in the step S24 of Fig. 10, the R, G and B values described in the mapping data MP15 are read out and stored, instead of referring to the illustration reference part 203.

In this case, the mapping table and the illustration image are combined, so that the illustration reference part 203 can be eliminated. Furthermore, since the R, G and B values are read out directly from the mapping data, instead of reading out the x, y coordinate values from the mapping data and then reading out the pixel data of the corresponding illustration image, one procedure of the process can be eliminated.

Furthermore, to display the illustration image of the vehicle, in general, a value 1.0 is often assigned as the rate of necessity. However, as in the example of Fig. 11, the rate of necessity of the illustration image is a value smaller than 1.0 and the illustration image is synthesized with another camera image so that a scale or an index can be displayed in a semi-transparent manner on the synthetic image.

<Example of basic synthetic image>

The mapping table can be classified roughly into two groups of a single map and a composite map. "Single map" refers to a map where camera images and images from a virtual point of view are correlated by the pixel level, using a predetermined space model (which will be described in detail later). "Composite map" will be described later.

The display mode of the image processing part 2 is determined by the type of the mapping table set in the image synthesizing part 200. This display mode can be switched manually or automatically.

A typical single map and an example of a synthetic image using the single map will be described below.

Vertical downward view (Figs. 12 to 14)

5 A road surface plane model is used as the space model. The position of the virtual point of view is above the vehicle, and the direction of the line of sight is directed straight downward. This example is characterized in that the distance can be perceived easily and this example can be used
10 advantageously for parking (perpendicular or parallel parking) or the like. Fig. 12 shows an image utilizing images from eight cameras. Fig. 13 shows an image utilizing images from four cameras. Fig. 14 shows an image utilizing images from two cameras.

15

Obliquely downward view (Fig. 15)

A road surface plane model is used as the space model. The position of the virtual point of view is above the vehicle, and the direction of the line of sight is directed
20 obliquely backward. The range of view can be changed freely by adjusting the angle of the line of sight. In this mode, the backward of the vehicle can be looked out extensively in the right position relationship. This mode can be used advantageously as a rear view monitor at regular running, or
25 to confirm safety at a low speed back-up such as the start of an operation for parking. At a low speed running, the range of view or the direction can be switched depending on the

speed.

Panorama (Figs. 16 and 17)

A cylindrical model is used as the space model. Fig. 5 16 is a forward panorama mode. The position of the virtual point of view is at the front edge of the vehicle, and the direction of the line of sight is straight ahead. In this mode, the state of the forward of the running direction can be seen, so that this mode can be utilized as a blind corner 10 view monitor. More specifically, when the vehicle goes into a large street from a narrow lane, this mode allows the state of the large street to be recognized at once.

Fig. 17 is a backward panorama mode. The position of the virtual point of view is at the rear edge of the vehicle, 15 and the direction of the line of sight is straight backward. In this mode, the backward portion of the vehicle can be looked out extensively as a 180 degree-panorama image. This mode can be used as a rear view monitor at running (especially, at high speed running).

20

Obliquely downward view + panorama (Fig. 18)

A road surface plane model and a cylindrical model are used as the space models. More specifically, as shown in Fig. 18, an image of a place near the rear of the vehicle is 25 displayed in the obliquely downward view mode using the road surface plane model, and an image of a place far from the rear of the vehicle is displayed in the panorama mode using

the cylindrical model. Thus, this mode can be used advantageously in applications both in the obliquely downward view mode and the panorama mode.

5 <Display automatic switching>

In the monitoring system of the present invention, more safe and comfortable driving can be supported by switching the mapping table described above in accordance with various driving scenes, as appropriated. Furthermore, in one driving
10 operation, it is essential for the driver to switch the mapping table in accordance with the ever-changing circumstances of the surrounding of the vehicle.

In other words, at least one of the position, the direction of the line of sight and the focal length of the
15 virtual point of view of the synthetic image is changed in accordance with the running state of the vehicle, so that the convenience for the driver can be improved.

Figs. 19(a) to 19(f) are views showing an example in which the height of the virtual point of view of the
20 synthetic image is changed. In the images shown in Figs. 19(a) to 19(f), the height of the virtual point of view is increased in descending order, and the display region including the vehicle becomes gradually wider. In other words, zoom-up is realized by lowering the height of the
25 virtual point of view, and zoom-down is realized by raising the height of the virtual point of view. Even if the focal length of the virtual point of view is changed, the synthetic

image can be changed in the same manner as in Figs. 19(a) to 19(f).

A first example of a trigger for switching the height of the virtual point of view can be a running speed of the vehicle. For example, the virtual point of view can be raised as the running speed of the vehicle is increased, so that a wider area can be displayed. On the other hand, the virtual point of view can be lowered as the running speed of the vehicle is reduced, so that a narrower area can be displayed. Alternatively, when the vehicle is provided with an object detecting sensor for measuring the distance between the vehicle and an obstacle, output signals from the object detecting sensor can be used as the trigger for switching. For example, the virtual point of view can be lowered as the distance between the vehicle and the detected obstacle is reduced, so that a narrower area can be displayed. On the other hand, the virtual point of view can be raised as the distance is increased, so that a wider area can be displayed. Furthermore, a switching switch may be provided so that the driver or another passenger can designate enlargement or contraction of the image via the switch.

Figs. 20(a) to 20(d) are views showing an example in which the direction of the line of sight of the virtual point of view of the synthetic image is changed. In the images shown in Figs. 20(a) to 20(d), the direction of the line of sight of the virtual point of view is changed gradually from oblique backward to vertical downward. With the change in

the direction of the line of sight, the model for generating the synthetic image is also changed. In other words, the region for the synthetic image of a quasi-cylindrical model is larger as the direction of the line of sight is inclined more obliquely, so that a farther place can be seen easily.

In Figs. 20(a) to 20(d), it can be said that with the change in the direction of the line of sight of the virtual point of view, capturing an image outside of the view range of the changed virtual point of view is controlled. In other words, using the quasi-cylindrical model, the image that is outside of the view range of the virtual point of view can be captured. Then, the presence or the absence of the capturing of the image that is outside of the view range of the virtual point of view, the size thereof, and the image capturing range are controlled in accordance with the running state of the vehicle.

An example of a trigger for switching the direction of the line of sight of the virtual point of view can be the running speed of the vehicle, input with a switch or the like, as in the case of switching the height of the virtual point of view. For example, when the running speed of the vehicle is low, the line of sight is oriented straight downward. As the running speed is increased, the direction of the line of sight is inclined so that more backward can be displayed.

Figs. 21(a) and 21(b) are views showing an example where the direction of the line of sight of the virtual point of view of the synthetic image is changed in accordance with

the steering angle of the vehicle. In the example of Figs. 21(a) and 21(b), the virtual point of view is rotated about the optical axis in accordance with the steering angle. Fig. 21(a) is a synthetic image when the gear is in reverse and the steering wheel is straight. In this case, the vehicle moves straight backward, and therefore the virtual point of view is set in such a manner that the vehicle in the synthetic image is straight, and the regions on the right and the left of the vehicle are equally displayed, so that the area behind the vehicle can be seen easily. On the other hand, Fig. 21(b) is a synthetic image when the gear is in back and the steering wheel is rotated left. In this case, the vehicle moves left backward, and therefore the virtual point of view is rotated about the optical axis so that the area to which the vehicle moves, that is, the right side, the right backward and the backward of the vehicle can be seen easily. Thus, safety is ensured further.

Figs. 22(a) and 22(b) are views showing an example of image switching in response to output signals from the object detecting sensor. Fig. 22(a) is a scene before the object detecting sensor detects an obstacle approaching the vehicle. When the object detecting sensor detects an obstacle approaching the vehicle, the image on the screen is switched to the image shown in Fig. 22(b). In other words, the image is enlarged on the display so that the distance between the vehicle and the detected obstacle is recognized more easily.

Thus, when the object detecting sensor detects an

obstacle, the image is displayed with enlargement / contraction / rotation, etc., that is effected step by step or continuously in accordance with the distance to the obstacle, so that the obstacle can draw the attention of the driver or the passenger. Furthermore, the position of the virtual point of view can be changed in accordance with the position in which the obstacle is located.

Furthermore, as shown in Fig. 23, the region in which the obstacle is located can be enlarged and displayed, and the region can be enclosed with a frame and displayed. Alternatively, the frame can be flashed, or the color inside the frame can be reversed. This ensures further that the attention of the driver or the passenger can be drawn. Display only with enclosure with a frame without enlarging the image makes it possible to draw the attention of the driver or the passenger. Furthermore, a warning sound can be produced together with the change in the screen display so that the presence of an obstacle can be informed of.

Fig. 24 shows another example of image switching in accordance with the results of detection of the object detecting sensor. In Fig. 24, when an obstacle is detected backward of the vehicle, the direction of the line of sight of the virtual point of view is changed from straight downward to slightly backward. This change makes it possible to watch the obstacle located backward of the vehicle more easily. Furthermore, the virtual point of view can be displaced in parallel so that the detected obstacle is in the

center of the synthetic image.

In Figs. 19 to 24, the synthetic images in the case where the virtual point of view is above the vehicle have been described. However, even if the virtual point of view is located in another position, the convenience of the driver can be improved by changing at least one of the position, the direction of the line of sight and the focal length of the virtual point of view in accordance with the running state of the vehicle. As other examples of the position of the virtual point of view, the position of the rear trunk or the position of the head of the driver can be used.

In Figs. 20(a) to 20(d), with change in the direction of the line of sight of the virtual point of view, capturing an image outside of the view range is controlled. However, with the change in the position or the focal length of the virtual point of view, capturing an image that is outside of the view range can be controlled. Furthermore, an image that is outside of the view range of the virtual point of view can be captured without using the models. Moreover, control of capturing an image that is outside of the view range of the virtual point of view may be only performed in accordance with the running state of the vehicle without changing the virtual point of view.

(Second example of an operation for generating a synthetic image)

Display image easily can be switched by changing the

mapping table to be used, as appropriate. However, in this case, to switch display image continuously, it is necessary to prepare a large number of mapping tables. For this reason, it is necessary to provide a storing part having a large storage capacity, which is unfavorable.

In this example, an original mapping table larger than a synthetic image is provided, and a mapping table that is cut out from this original mapping table is used to synthesize the synthetic image. In this case, continuous switching of display image easily can be realized by changing the mapping table to be cut out, as appropriate.

Fig. 25 is a diagram showing the configuration of a monitoring system of this example. This configuration is different from that shown in Fig. 7 in that based on the coordinates of the pixel of the synthetic image output from a timing generating part 205 and the region designation information of the mapping table set by a display pattern setting part 220A, a map region setting part 302 generates an element of the corresponding mapping table and outputs the element to a mapping table reference part 202. In the mapping table reference part 202, the original mapping table stored in an original mapping table storing part 301 included in the display pattern storing part 210A is set by the display pattern setting part 220A.

More specifically, in the first example described above, in the step S13 shown in Fig. 8, the mapping data in the same position as the pixel of the synthetic image to be output at

present that is set by the timing generating part 205 is read out. In this example, after setting the region of the mapping table to be utilized on the original mapping table, the mapping table corresponding to the pixel of the synthetic
5 image is read out.

The method for reading out the mapping data in this example will be described below. Figs. 26(a) to 26(d) and Figs. 27(a) to 27(g) schematically show the relationship between the synthetic image and the original mapping table in
10 this example. In the example of Figs. 26(a) to 26(d), parallel displacement of the synthetic image can be realized by fixing the size of the region to be cut out from the original table to the same size as that of the synthetic image and changing the offset value. In the example of Figs.
15 27(a) to 27(d), enlargement and contraction of the synthetic image can be realized by changing the size of the region to be cut out from the original table and the read-out step of the element.

First, the case where parallel displacement of the
20 synthetic image will be described with reference to Figs. 26(a) to 26(d).

The synthetic image shown in Fig. 26(a) has the size of a width of W_DISP and a height of H_DISP , and the original mapping table shown in Fig. 26(b) has the size of a width of
25 W_MAP and a height of H_MAP . The original mapping table in this example is a table for creating an image in which a wide range of the surrounding of the vehicle is overlooked from

the virtual point of view in the sky above the vehicle. In the first example described above, if the focal length is constant, this corresponds to enlargement of the size of a projection plane from (W_DISP, H_DISP) to (W_MAP, H_MAP) with
5 a constant distance between the virtual point of view and the projection plane. The original mapping table can be constructed in this manner. By enlarging the projection plane, the original mapping table can contain information on a wider range of areas. Fig. 26(d) is an image obtained by
10 replacing the elements of the mapping table by the corresponding camera images and the illustration images.

Next, the display pattern setting part 220A designates a region to be used as the mapping table for generating the synthetic image by an offset (off_x, off_y) from the origin
15 (0, 0) on the original mapping table. A region MPT of a size of (W_DISP, H_DISP) with the point (off_x, off_y) as the start point is used as the mapping table for image synthesis. The mapping data at the position obtained by adding this offset (off_x, off_y) to the X, Y coordinates of the pixel obtained
20 by raster scanning of the synthetic image is read out from the mapping table reference part 202 and is output to the image synthesizing part 201. The synthesis processing of the pixel is performed according to the flowchart of Fig. 10 as in the first example. Fig. 26(c) is a synthetic image
25 obtained with the mapping table MPT shown in Fig. 26(b).

In the case where the coordinates added with the offset exceeds the range of the original mapping table, the pixel

synthesizing part 201 is notified and display is performed in such a manner that a predetermined color (e.g., black) is used as the value for the pixel so that the region can be recognized.

5 This example makes it possible to generate a synthetic image when the virtual point of view is displaced in parallel to the road surface without increasing the number of the mapping tables, in the case where the virtual point of view is positioned so that it overlooks vertically from the above
10 of the vehicle to the road surface, and a road surface plane model is used. In order words, in the first example described above, each of the virtual points of view displaced in parallel needs a corresponding mapping table. However, in this example, one original mapping table is sufficient. For
15 example, when displacing the virtual point of view for each pixel for smooth displacement of the point of view, in the first example, a large number of mapping tables corresponding to all the movement steps are required. However, in this example, moving the virtual point of view for each pixel can
20 be realized simply by changing the start position (off_x, off_y) at which the mapping table is cut out in one wide range original mapping table. Moreover, in this example, for example, when changing the position of the virtual point of view by dialing or changing the position of the virtual point
25 of view toward the direction of an obstacle in proportion to the magnitude of the output of the obstacle detecting sensor, the position of the virtual point of view can be changed in a

large number of steps, so that a synthetic image easily can be generated in accordance with the circumstances.

In this example, the virtual point of view is displaced in parallel in a large number of steps, so that there is no need of using a large number of mapping tables. Therefore, the memory for storing the mapping tables only has to have a capacity for storing one original mapping table. Furthermore, in the first example, it takes time to switch or set the mapping tables, whereas in this example, setting offset is only required. Thus, high speed processing can be achieved.

Next, the case where the synthetic image is enlarged or contracted in the same manner will be described with reference to Figs. 27(a) to 27(g).

In Figs. 27(a) to 27(g), the timing generating part 205 is assumed to designate the coordinates (x, y) of a pixel P1 of a synthetic image shown in Fig. 27(a). The display pattern setting part 220A designates a read-out step (step_x, step_y) of an element as well as a start position (off_x, off_y) of a region. In this case, if the coordinates of the mapping data MD corresponding to the pixel P1 is (u, v), the coordinates (u, v) can be obtained by the following equation.

$$u = \text{step_x} * x + \text{off_x}$$

$$v = \text{step_y} * y + \text{off_y}$$

The synthetic image can be enlarged or contracted smoothly by changing the value of the read-out step (step_x, step_y). When the region of the mapping table that is cut out

from the original mapping table changes to MPT1, MPT2, MPT3, and MPT4 in accordance with the read-out step (step_x, step_y), the synthetic image is changed to the images shown in Figs. 27(d), 27(e), 27(f) and 27(g).

5 When the coordinates (u, v) exceed the range of the original mapping table, for example, a designated color is output in the same manner as in the case of the parallel displacement described above. Values other than integers can be used as the value of the read-out step (step_x, step_y).
10 In this case, the values of (u, v) as a result of calculation are converted to integers.

 According to the method for enlargement and contraction of this example, the same synthetic image as in the case where the range of view is enlarged or contracted by changing
15 the height or the focal length of the virtual point of view can be generated, when the virtual point of view is positioned so that it overlooks vertically from the above of the vehicle to the road surface, and a road surface plane model is used.

20 For example, when a part of the original image is enlarged for display in response to an instruction or of the driver or a sensor input, an enlarged image is not abruptly output, but the image is enlarged smoothly by using the method of this example. As a result, it is easily recognized
25 as to which part of the region of the original image the enlarged image corresponds to.

 Furthermore, parallel displacement as well as

enlargement and contraction of an image can be realized by changing the offset value as well as changing the read-out step.

In general, there is no need of restricting the region of the mapping table to a square. In other words, the display pattern setting part 220A can designate the region of a mapping table by the coordinates of four vertices of a quadrangle.

In Fig. 28, the region of a mapping table has a shape of a convex quadrangle, and is designated by four points **n1**, **n2**, **n3**, and **n4**. In this case, the coordinates (u, v) of the mapping data **MD** corresponding to a pixel **P1** of the coordinates (x, y) of the synthetic image can be obtained in the following manner.

First, the coordinates of a point **na** that divides the line segment connecting vertices **n1** and **n2** in a ratio of $(y / H_DISP : 1 - y / H_DISP)$ are obtained. Similarly, the coordinates of a point **nb** that divides the line segment connecting vertices **n3** and **n4** in a ratio of $(y / H_DISP : 1 - y / H_DISP)$ are obtained. Then, when the coordinates of a point that divides the line segment connecting vertices **na** and **nb** in a ratio of $(x / W_DISP : 1 - x / W_DISP)$ are obtained, they are the coordinates (u, v) of the corresponding mapping data **MD**.

This manner of designation makes it possible to designate regions of arbitrary mapping tables, including parallel displacement, enlargement, contraction and rotation.

According to the method of this example, a synthetic image that matches precisely with the change of the virtual point of view such as parallel displacement of the virtual point of view, enlargement and contraction of the range of view or rotation parallel to the road surface can be generated, when a road surface plane model is used, and the virtual point of view is positioned so that it overlooks vertically from the above of the vehicle to the road surface. When the model or the direction of the virtual point of view is different, it is not necessarily possible to generate a synthetic image that matches precisely with the change of the virtual point of view. However, in this case as well, it is possible to generate a synthetic image approximate to the change of the virtual point of view, so that this method is significantly advantageous.

<A plurality types of image display>

The convenience of the driver can be improved by displaying a plurality of types of synthetic images on one screen, or displaying synthetic images and camera images on one screen at the same time. For example, the driver can recognize precisely the circumstances surrounding the vehicle without switching the screen display by displaying a place near the vehicle and a place far from the vehicle at the same time; displaying images in different directions at the same time; or displaying the entire body of the vehicle and a part of the enlarged vehicle at the same time.

Such display of a plurality of types of images easily can be realized with a composite map. A "composite map" refers to a mapping table obtained by cutting out necessary portions in the single map for appropriate transformation, 5 attaching the cut-outs, or attaching camera images to the single map. The image display described below can be realized easily with a composite map. However, with respect to image display other than that, composite maps corresponding to various driving scenes can be created by 10 combining at least two single maps, or a single map and a camera image.

Herein, an example of displaying an image including a downward view image viewed from the virtual point of view set above the vehicle as a close view image showing the vehicle 15 and the surroundings thereof, using a road surface plane model, and a distant view image showing areas farther than the surrounding areas of the vehicle showing this downward view image will be described. Fig. 29 shows camera images that constitute the base of the description herein.

20 Fig. 30 is an example where camera images showing oblique backward as second images are attached on the right and the left of the downward view image as the first image. In this example, the point of view of the second image is different from the virtual point of view of the first image 25 in the position, the direction of the line of sight and the focal length. In the image of Fig. 30, the image of a camera 2 shooting the scenery obliquely backward on the right is

arranged on the right side of the downward view image with left-right reversal. The image of a camera 6 shooting the scenery obliquely backward on the left is arranged on the left side of the downward view image with left-right reversal.

5 In other words, the images of cameras 2 and 6 installed in the vicinity of the right and left door mirrors are arranged with left-right reversal so that the images are displayed as if they were seen on the door mirrors. Therefore, the driver can grasp the circumstances surrounding the vehicle
10 intuitionallly with the same sense as looking at the door mirror. The images can be displayed without left-right reversal.

Fig. 31 is an example where a downward view image showing a narrow range as the first image and a downward view
15 image showing a wide range as the second image are displayed side by side. In this example, the virtual point of view of the second image is different from that of the first image in the height or the focal length. The image of Fig. 31 allows immediate grasp of both a place near the vehicle in detail
20 and a wider range in the thumbnail manner.

Fig. 32 is an example where obliquely downward view images of the forward, the backward, the right, and the left of the vehicle as the second images are attached around the downward view image as the first image. In this example, the
25 virtual point of view of the second image is different from that of the first image in the direction of the line of sight. Fig. 33 is an example where images that might be obtained

through a fisheye lens with a quasi-cylindrical model as the second images are attached around the downward view image as the first image. In this example, the second images are different from the first image in the model. Fig. 34 is an example where panorama images of the forward, the backward, the right, and the left of the vehicle as the second images are attached around the downward view image as the first image. In this example, the second images are different from the first image in the position of the virtual point of view and the model. The images of Figs. 32 to 34 allow the driver to grasp the distance with respect to the place near the vehicle and to look out extensively with respect to the place far from the vehicle.

It is not necessary to attach the distant view image on all the sides of the forward, backward, right and left of the downward view. A distant view image can be displayed only on the side that is desired to be seen, for example, only on the right side, or the backward.

As shown in Fig. 35, when the obliquely downward view images are attached around the downward view image on the forward, backward, right and left thereof, blank portions are provided at the four corners of the display region, so that no continuity of the obliquely downward view images can be emphasized.

When image display as shown in Figs. 32 to 35 is performed, display can be blurred by subjecting the surrounding distant images to filter processing. This allows

the driver to concentrate his/her attention on the surroundings of the vehicle. Furthermore, distortion in the surrounding distant images does not stand out.

Such partial blur processing is advantageous in the case of image display with a single map as well. For example, in the case of the downward view image as shown in Fig. 5, the same effect can be obtained by performing blur processing to the surrounding areas in which other parked vehicles are displayed without performing blur processing to the vehicle and the surroundings thereof. It is preferable to set an area within 10m from the vehicle as the region that is not subjected to blur processing. It is also possible to increase the intensity of blur with increasing the distance from the vehicle.

The image of Fig. 31 can be a synthetic image including a first image showing the surroundings of the vehicle and a second image obtained by enlarging at least a part of the region shown in the first image. The first image can show a part of the vehicle instead of the whole body of the vehicle, or can show a part of the surroundings of the vehicle.

Furthermore, the display screen can be a multiwindow display, and the synthetic image as described above, camera images, images showing the position of the virtual point of view, letter information or the like can be displayed in subwindows. This achieves easier grasp of the circumstances of the surroundings of the vehicle, and thus the convenience of the driver can be improved.

There may be many methods for display on a multiscreen. For example, as shown in Fig. 36, the image showing the position of the virtual point of view can be displayed on a subwindow together with a camera image or a synthetic image. 5 Thus, the position of the virtual point of view easily can be grasped.

Furthermore, for example, when an object detecting sensor detects an obstacle, a warning mark showing the position of the obstacle can be displayed on the camera image or the synthetic image on each subwindow. In addition, the position of the obstacle can be displayed with letters on another subwindow. 10

<Display of a blind spot region and a region of the vehicle >

15 Example 1

Fig. 37 is an example of mask data as region data indicating camera images and projection regions of the vehicle in the camera images. As shown in Fig. 37, the portion where the vehicle is projected in each camera image is identified and mask data showing the identified projection region of the vehicle are previously stored in the image processing part 2. The black portion in the mask data shown in Fig. 37 is the projection region of the vehicle. The projection region of the vehicle previously can be determined 20 uniquely, if the specification and the directions of the cameras, and the shape of the vehicle are determined. 25

Fig. 38(a) is a vertically downward view image

synthesized with the camera images of Fig. 37. In the synthetic image shown in Fig. 38(a), the vehicle is projected white in the center of the image, which makes the image unclear.

5 Therefore, the mask data of each camera image are converted to the images viewed from the virtual point of view, and in the synthetic image, the projection region of the vehicle is blacked out. As a result, the image as shown in Fig. 38(b) can be obtained, which makes the image better.

10 In Fig. 38(a), the vehicle is projected in the center of the image, which makes the image unclear. In addition, an actual place in which the vehicle is located is unclear. This makes driving difficult. Therefore, the illustration image or the actual image of the vehicle is superimposed on
15 the position on which the vehicle is actually located. For example, the image processing part 2 previously stores the illustration image or the actual image of the vehicle that is presupposed to be viewed from the standard virtual point of view, and this image is converted to an image viewed from the
20 virtual point of view of the synthetic image to be displayed. Then, the converted image can be superimposed. As a result, the image shown in Fig. 38(c) can be obtained, and the size of the vehicle or the position relationship relative to the objects surrounding the vehicle can be recognized at once.
25 Conversion of the image of the vehicle easily can be realized with the above-described mapping table.

 In this case, for example, the virtual point of view

provided above the vehicle, the virtual point of view positioned on the side, the virtual point of view provided forward or backward of the vehicle can be used as the standard virtual point of view. Furthermore, a plurality of
5 standard virtual points of view can be provided and an image can be prepared with respect to each of the plurality of standard virtual points of view. When the position of the virtual point of view for generating the synthetic image is determined, the standard virtual point of view that provides
10 the smallest distortion in the image during conversion of the image may be selected based on the position relationship of the virtual point of view and each standard virtual point of view.

Instead of attaching the illustration or the actual
15 image of the vehicle, a three-dimensional model with a surface model or a solid model that are known in the field of CAD/CAM or CG can be attached to the synthetic image. Also in this case, images showing three-dimensional models viewed from the standard virtual point of view are previously
20 prepared, and this image is converted to an image viewed from the virtual point of view of the synthetic image to be displayed. Then, the converted image can be superimposed. This conversion easily can be realized with the above-described mapping table.

25 Furthermore, as the image showing the region in which the vehicle is actually located, the synthetic image generated from the camera image itself may be utilized.

Furthermore, a part of the vehicle, for example, only the bumper portion may be displayed in the synthetic image, and for other portions, illustrations or actual images may be attached.

5

Example 2

The synthetic image viewed from the virtual point of view may include a region that does not belong to any camera coverage, and may include a region that cannot be captured by the camera because of interruption of the vehicle.

10

In order to solve this problem, in Example 1 described above, the synthetic image can be more clear by assigning predetermined pixel data to the projection region of the vehicle and blacking out the region.

15

In this example, as shown in Fig. 39, when the camera image on which the vehicle is shown is converted to an image from the virtual point of view without any additional processing, the converted image of the vehicle is included in the synthetic image, which make the image unclear (A1). In this case, the image can be clear by blacking out the region where the vehicle is shown.

20

However, in the image from the virtual point of view, a part of the vehicle may be shown in a portion where the vehicle does not exist (A2). In this case, it is not preferable to black out the portion of the vehicle in the image from the virtual point of view, because the portion that should be seen is also eliminated. This problem can

25

arise when the space model used for conversion of the original camera image to an image from the virtual point of view is different from that in the actual world that is shown on the camera (simplified in most cases). Therefore, in order to solve this problem with respect to its principle, it is necessary to calculate information on the depth of the actual world in realtime, which requires high speed operation ability in the apparatus. Therefore, it is difficult to carry this out.

Therefore, this problem can be solved by the following method.

Whether or not the pixel of the synthetic image is included in the projection region of the vehicle is determined by referring to the mask data that makes a pair with the original camera image. Generation of this pixel is switched depending on whether or not the pixel is included in the projection region of the vehicle. More specifically, the mask data is not converted to an image from the virtual point of view, but the mask data in the form of the original camera image is used.

Fig. 40 shows an example of the mask data. As shown in Fig. 40, mask data indicating a region that is not used for synthesis of an image from the virtual point of view such as the projection portion of the vehicle is provided with respect to each camera image.

In this case, for example, when the pixel data of a camera image for generation of a synthetic image is referred

to, mask data corresponding to this camera image is also referred to. When the pixel is included in the projection region of the vehicle, generation of the pixel is not performed, and a process such as assigning a specific color
5 that can indicate that the region is a blind spot region can be performed.

As the mapping data MP14 described above, the mapping table itself can have information as to whether or not the pixel of a synthetic image is included in a blind spot region.
10 In this case, in synthesis of an image from the virtual point of view, there is no need of referring to the mask data for every frame, so that high speed processing can be realized. Furthermore, this provides the advantage that there is no need of providing a storage part for storing the mask data.

15 Fig. 41 shows an example of the results of image synthesis. In the synthetic image shown in Fig. 41, a vehicle region where the vehicle is located and a blind spot region around the vehicle are shown. Indicating the vehicle region makes it easy for the driver to grasp the position
20 relationship or the distance between the vehicle and the circumstances of the surroundings. Furthermore, the area that is hardly seen directly from the driver's seat can be confirmed by the synthetic image. Moreover, indicating the blind spot region makes it possible for the driver to
25 recognize the area that is not shot by any of the cameras, so that safety can be improved.

It is not necessary to indicate the entire vehicle

region where the vehicle is located, and a part of the vehicle region may be indicated. For example, when the number of cameras to be installed is limited so that only the vehicle or a part thereof can be captured, only the captured
5 part of the vehicle region and the surrounding blind spot regions are indicated. Alternatively, when a specific part around the vehicle is enlarged for display, a part of the vehicle to be displayed and the surrounding blind spot region are indicated.

10 Furthermore, instead of the blind spot region, an attention drawing region for drawing the attention of the driver or the passengers of the vehicle may be indicated. This attention drawing region may be a region including a blind spot region around the vehicle that is not shot by any
15 of the cameras, or may be a region corresponding to the blind spot region itself. The attention drawing region may be a region indicating a part of the surrounding of the vehicle.

The attention drawing region can be previously set by using the position relationship with the vehicle region,
20 regardless of the camera shooting coverage. Therefore, synthesis can be performed by simple processing. When the attention drawing region includes the blind spot region, a portion captured by a camera that is not in a blind spot region can be hidden as the attention drawing region.
25 However, for example, the attention drawing region can be made semi-transparent for display in combination with the blind spot region.

Fig. 42 is a diagram showing the procedure of generating mapping data in the case where the blind spot region is obtained with mask data, and illustration images are attached. In Fig. 42, <PT1> is a pixel of a synthetic image that is generated from one camera image. <PT2> is a pixel of a synthetic image for which two camera images are referred to, but one of the camera images is removed for projection of the vehicle, and the synthetic image is generated from the remaining one camera. <PT3> is a pixel of a synthetic image for which one camera image is referred to, and the camera image is removed for projection of the vehicle. <PT4> is a pixel of a synthetic image for which one camera image is referred to, but the camera image is removed for projection of the vehicle, and an illustration image of the vehicle is attached.

First, in a step 1, the reference coordinates and the rate of necessity are calculated. With respect to the pixels of the synthetic image, the reference coordinates are calculated, regarding all the camera images. This calculation is performed by geometric operation, which will be described later. In this case, when the obtained reference coordinates are outside the shooting coverage of the camera image (that is, a blind spot), $(-1, -1)$ is described as the coordinates. Also here, the number of cameras that are referred to is obtained, and the inverse of that number is assigned as the rate of necessity. The rate of necessity can be assigned in another method or assigned by

manual input. In the step 1, the results show that <PT1> refers to camera 6, <PT2> refers to camera 4 and 5, <PT3> refers to camera 6, and <PT4> refers to camera 2.

Next, in a step 2, processing of the blind spot is performed by referring to the mask data indicating the projection region of the vehicle. In the mask data corresponding to cameras other than the camera whose coordinate values are (-1, -1), it is determined whether or not the point indicated by the coordinate value belongs to the projection region of the vehicle. When it belong to the projection region of the vehicle, the coordinate values are converted to (-1, -1). With this conversion, the value of the rate of necessity is calculated again when the number of cameras to be referred to is reduced.

With respect to <PT1>, a point (450, 200) in the mask data of the camera 6 does not belong to the projection region of the vehicle, as shown in Fig. 43(d), so that the coordinate values are not converted. With respect to <PT2>, a point (150, 280) in the mask data of the camera 4 belongs to the projection region of the vehicle, as shown in Fig. 43(b), so that the coordinate values of the camera 4 are converted to (-1, -1). On the other hand, a point (490, 280) in the mask data of the camera 5 does not belong to the projection region of the vehicle, as shown in Fig. 43(c), so that the coordinate values of the camera 5 are not converted. Then, the rate of necessity thereof is converted to "1". With respect to <PT3>, a point (110, 250) in the mask data of

the camera 6 belongs to the projection region of the vehicle,
as shown in Fig. 43(d), so that the coordinate values of the
camera 6 are converted to (-1, -1). With respect to <PT4>, a
point (600, 290) in the mask data of the camera 2 belongs to
5 the projection region of the vehicle, so that the coordinate
values of the camera 4 are converted to (-1, -1).

Next, in a step 3, redundant data is organized to
obtain the minimum necessary data for image synthesis. First,
all the camera numbers having coordinate values of (-1, -1)
10 are changed to "-1". Then, when all the camera numbers are
"-1", these data are integrated to one (<PT3>, <PT4>). When
camera numbers other than "-1" are present, data having a
camera number of -1 are removed (<PT1>, <PT2>).

In a step 4, an illustration image of the vehicle is
15 attached. With respect to the pixel of the synthetic image
for attaching the illustration image of vehicle, the camera
number of the mapping data is converted to "99", and the
reference coordinates of the illustration image are set. In
this example, <PT4> is the pixel for attaching the
20 illustration image of vehicle, and therefore the camera
number is converted to "99", and the coordinate values are
converted to the reference coordinate values (360, 44) of the
illustration image.

Fig. 44(a) is an example of a synthetic image in the
25 case where the mapping data at the end of the step 1 is used.
Fig. 44(b) is an example of a synthetic image in the case
where the mapping data at the end of the step 3 is used. Fig.

44(c) is an example of a synthetic image in the case where the mapping data at the end of the step 4 is used.

Fig. 45 is a diagram showing a procedure of generating mapping data in the case where an attention drawing region is designated without using the mask data. In Fig. 45, <PT5> is a pixel in a synthetic image generated from one camera image. <PT6> is a pixel in a synthetic image on which an attention drawing region is designated. <PT7> is a pixel in a synthetic image on which an attention drawing region is designated, but an illustration image is attached.

First, in a step 1', an initial mapping table is generated. This is performed by the processing of the steps 1 and 3 shown in Fig. 42.

Next, in a step 2', an attention drawing region is designated. A synthetic image is created using the initial mapping table generated in the step 1', and an attention drawing region is designated in this synthetic image.

Next, in a step 3', the mapping data corresponding to the attention drawing region is rewritten. In the mapping data corresponding to the attention drawing region designated in the step 2', the camera number is converted to "-1" and the coordinates are converted to (-1, -1). Then, when the number of the cameras that are referred to is reduced, the value of the rate of necessity is calculated again.

Then, in a step 4', an illustration image of the vehicle is attached. In this example, since <PT7> is a pixel for attaching an illustration image, the camera number is

converted to "99" and the coordinate values are converted to the reference coordinates value (360, 44).

Fig. 46(a) is an example of a synthetic image in the case where the mapping data at the end of the step 1' is used.

5 Fig. 46(b) is an example of a synthetic image in the case where the mapping data at the end of the step 3' is used.

Fig. 46(c) is an example of a synthetic image in the case where the mapping data at the end of the step 4' is used.

In this manner, a process such as superimposing the
10 image of the vehicle on the synthetic image, assigning a specific color to the entire blind spot region or the entire attention drawing region can be performed easily. When setting an attention drawing region, a predetermined attention drawing region is synthesized without referring to
15 the mask data with respect to the cameras, so that a synthetic image can be generated more simply. On the other hand, when setting a blind spot region, the mask data with respect to the cameras are referred to, so that all the circumstances of the surroundings of the vehicle captured by
20 the cameras can be reflected on the synthetic image.

In the above description, the monitoring system and the image processing apparatus of the present invention are applied to vehicles. However, the present invention also can be applied easily to movable bodies other than vehicles such
25 as airplanes or ships. Moreover, the cameras can be installed in places to be monitored other than movable bodies, such as stores, houses, and showrooms.

The positions or the number of the plurality of cameras are not limited to those shown in this specification.

All or part of the functions of the image processing apparatus of the present invention may be realized with a dedicated hardware or may be realized with software. Moreover, recording media or transmission media storing programs for executing all or part of the functions of the image processing apparatus of the present invention on a computer can be utilized.

10

<Geometric transformation>

In order to create a mapping table for synthetic images, it is necessary to determine the coordinates of a pixel of each camera image corresponding to each pixel of a synthetic image viewed from a virtual point of view.

For this purpose, first, a world coordinate system (X_w , Y_w , Z_w) corresponding to each pixel of a synthetic image from a virtual point of view is obtained. Then, the coordinates of pixels of a camera image corresponding to three-dimensional coordinates of the world coordinate system is obtained. This manner of using the two steps is convenient.

The ultimately required relationship is only a relationship between each pixel of a synthetic image from a virtual point of view and a pixel of each camera, and there is no reason for limiting to the mapping table obtained via the world coordinate system. However, the mapping table obtained via the world coordinate system clarifies the

significance of the synthetic image in the world coordinate system, which is a coordinate system in the actual world, so that this is important in that the synthetic image that easily can be correlated with the circumstances of the surroundings with the actual distance or the position relationship can be generated.

The world coordinates (X_w, Y_w, Z_w) corresponding to the coordinates (V_x, V_y, V_z) of the point of view of the synthetic image can be obtained by Equation (1):

$$\begin{pmatrix} X_w \\ Y_w \\ Z_w \end{pmatrix} = R_v \begin{pmatrix} V_x \\ V_y \\ V_z \end{pmatrix} + T_v$$

$$\text{where } R_v = \begin{pmatrix} r_{v11} & r_{v12} & r_{v13} \\ r_{v21} & r_{v22} & r_{v23} \\ r_{v31} & r_{v32} & r_{v33} \end{pmatrix}, \quad T_v = \begin{pmatrix} T_{xv} \\ T_{yv} \\ T_{zv} \end{pmatrix} \quad (1)$$

where as the parameters indicating the position and the direction of a virtual point of view, the coordinates in the world coordinate system of the point of view is represented by the position vector $T_v = (T_{xv}, T_{yv}, T_{zv})$, and the direction of the line of sight is indicated by a rotating matrix R_v having three rows and three columns indicating rotation to match the view plane coordinate system to the orientation of the world coordinate system.

Fig. 47 is a schematic view illustrating the relationship between the viewpoint coordinate system and the world coordinate system.

As shown in Fig. 48, the rotating matrix R_v is as follows:

$$R_v = \begin{bmatrix} \cos \alpha_v & 0 & -\sin \alpha_v \\ 0 & 1 & 0 \\ \sin \alpha_v & 0 & \cos \alpha_v \end{bmatrix} \begin{bmatrix} 1 & 0 & 0 \\ 0 & \cos \beta_v & -\sin \beta_v \\ 0 & \sin \beta_v & \cos \beta_v \end{bmatrix} \begin{bmatrix} \cos \gamma_v & \sin \gamma_v & 0 \\ -\sin \gamma_v & \cos \gamma_v & 0 \\ 0 & 0 & 1 \end{bmatrix} \quad (2)$$

where the angle of horizontal rotation (azimuth) of the line of sight with respect to the Y-Z plane of the world coordinate system is α_v , the inclination angle (elevation angle) of the line of sight with respect to the X-Z plane is β_v , and the rotation (twist) around the optical axis of the camera is γ_v .

On the other hand, the relationship between the V_{xe} and V_{ye} of the viewpoint coordinate system (V_{xe} , V_{ye} , V_{ze}) of the virtual point of view and the two-dimensional coordinate U_v and V_v on the projection plane can be represented by Equation (3) using the focal length f_v from perspective projection transformation.

$$u_v = \frac{f_v}{V_{ze}} V_{xe}$$

$$v_v = \frac{f_v}{V_{ze}} V_{ye} \quad (3)$$

The focal length may be represented by the unit of mm or inch corresponding to the size, assuming that the projection plane is a film or a CCD, or may be represented by the pixels corresponding to the size of the synthetic image. In this example, the projection plane is normalized to have a

width of 2 and a height of 2 with the projection center as its center, and the focal length corresponding thereto is used.

Therefore, as for the relationship between the
 5 coordinates on the projection plane and the pixels of the synthetic image, if the horizontal width of the image is W_v pixels, and the vertical width is H_v pixels, the coordinates (U_v, V_v) on the projection plane corresponding to the pixel positioned (S_v, T_v) from the upper right of the image can be
 10 obtained by:

$$\begin{aligned} U_v &= 2 \times S_v / W_v - 1 \\ V_v &= 2 \times T_v / H_v - 1 \end{aligned} \quad (4)$$

As a result, the three-dimensional coordinates $(X_w, Y_w,$
 15 $Z_w)$ of the world coordinate system corresponding to an arbitrary pixel (S_v, T_v) of the synthetic image can be obtained from Equations (1) to (4), the position of the camera T_{xv}, T_{yv}, T_{zv} , the direction of the camera $\alpha_v, \beta_v, \gamma_v$, and the focal length f_v by Equation (5).

20

$$\begin{pmatrix} x_w \\ y_w \\ z_w \end{pmatrix} = R_v \begin{pmatrix} \frac{V_{ze}}{f_v} u_v \\ \frac{V_{ze}}{f_v} v_v \\ V_{ze} \end{pmatrix} + T_v = \begin{pmatrix} (\frac{2S_v - W_v}{f_v \cdot W_v} r_{v11} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v12} + r_{v13}) V_{ze} + T_{xv} \\ (\frac{2S_v - W_v}{f_v \cdot W_v} r_{v21} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v22} + r_{v13}) V_{ze} + T_{yv} \\ (\frac{2S_v - W_v}{f_v \cdot W_v} r_{v31} + \frac{2T_v - H_v}{f_v \cdot H_v} r_{v32} + r_{v33}) V_{ze} + T_{zv} \end{pmatrix} \quad (5)$$

However, in Equation (5), the depth V_{ze} corresponding to the coordinates (S_v, T_v) of the synthetic image is undetermined. In other words, it is necessary to determine

the depth value from each pixel to the object to be captured in the synthetic image.

If the three-dimensional shape of the object viewed from the virtual point of view can be known, the depth of each pixel can be obtained. However, this is difficult in general. Therefore, a model for the shape of the object viewed from the virtual point of view is assumed to obtain V_{ze} , and the relationship between the coordinates of the synthetic image and the three-dimensional coordinates of the world coordinate system is obtained.

- Road surface plane model-

As one example thereof, the case where an object is on the road surface plane in contact with the vehicle will be described.

If it is assumed that all objects are present on a plane (road surface) of the world coordinate system, the three-dimensional coordinates (X_w , Y_w , Z_w) of the world coordinate system satisfies the following equation of a plane.

$$ax_w + by_w + cz_w + d = 0 \quad (6)$$

Therefore, V_{ze} can be obtained by substituting Equation (6) in Equation (5) as follows.

$$V_{ze} = -f_v \frac{aT_{xv} + bT_{yv} + cT_{zv} + d}{aQ_1 + bQ_2 + cQ_3}$$

$$\text{where } Q_1 = r_{v11} \frac{2S_v - W_v}{W_v} + r_{v12} \frac{2T_v - H_v}{H_v} + r_{v13} f_v$$

$$\begin{aligned}
Q_2 &= r_{v21} \frac{2S_v - W_v}{W_v} + r_{v22} \frac{2T_v - H_v}{H_v} + r_{v23} f_v \\
Q_3 &= r_{v31} \frac{2S_v - W_v}{W_v} + r_{v32} \frac{2T_v - H_v}{H_v} + r_{v33} f_v
\end{aligned} \tag{7}$$

Therefore, from the coordinates (Sv, Tv) of the pixel
 5 of the synthetic image from the virtual point of view, the
 corresponding three-dimensional coordinates (Xw, Yw, Zw) of a
 plane of the world coordinate system can be obtained by
 substituting Equation (7) in Equation (5).

The coordinates of each pixel of each camera image
 10 corresponding to the three-dimensional coordinate system (Xw,
 Yw, Zw) in the world coordinate system can be obtained by
 substituting the parameters of Tx, Ty, Tz, α, β, and γ
 corresponding to the position and the direction of each
 camera in the relative equation similar to Equation (1).

15 For example, if the position of the camera 1 is Tx1,
 Ty1, and Tz1, and the direction thereof is α1, β1, and γ1,
 the camera coordinate system Xel, Yel, and Zel of the camera
 1 corresponding to the pixel (Sv, Tv) of the synthetic image
 can be calculated with Equation (8).

20

$$\begin{bmatrix} X_{e1} \\ Y_{e1} \\ Z_{e1} \end{bmatrix} = R_1^{-1} \left(\begin{bmatrix} X_w \\ Y_w \\ Z_w \end{bmatrix} - \begin{bmatrix} T_{x1} \\ T_{y1} \\ T_{z1} \end{bmatrix} \right)$$

$$\text{where, } R_1^{-1} = \begin{bmatrix} \cos \gamma_1 & -\sin \gamma_1 & 0 \\ \sin \gamma_1 & \cos \gamma_1 & 0 \\ 0 & 0 & 1 \end{bmatrix} \begin{bmatrix} 1 & 0 & 0 \\ 0 & \cos \beta_1 & \sin \beta_1 \\ 0 & -\sin \beta_1 & \cos \beta_1 \end{bmatrix} \begin{bmatrix} \cos \alpha_1 & 0 & \sin \alpha_1 \\ 0 & 1 & 0 \\ -\sin \alpha_1 & 0 & \cos \alpha_1 \end{bmatrix} \quad (8)$$

The relationship between this camera coordinate system and the coordinate system (U1, V1) of the camera image can be
5 calculated with Equation (3) as follows.

$$\begin{aligned} U1 &= f1 / z_{e1} \times X_{e1} \\ V1 &= f1 / z_{e1} \times Y_{e1} \end{aligned} \quad (9)$$

where the focal length of the camera 1 is f1. The pixel of the corresponding camera image can be calculated
10 with Equation (10), assuming that the size of the camera image is H1 pixels in the vertical length and W1 pixels in the horizontal width, the aspect ratio is 1: 1, and the center of the camera is the center of the image.

$$\begin{aligned} S1 &= W1 / 2 \times (Uv + 1) \\ T1 &= H1 / 2 \times (Vv + 1) \end{aligned} \quad (10)$$

With the above procedure, the pixel (S1, T1) of the image of the camera 1 corresponding to the pixel (Sv, Tv) of
20 the image from the virtual point of view can be obtained. The pixel coordinates (Sn, Tn) corresponding to (Sv, Tv) with respect to a general camera n other than the camera 1 can be calculated in the same manner. In the parameter table, the camera number n and its coordinates (Sn, Tn) are written by
25 selecting one or a plurality of optimal coordinates among

them, depending on various conditions, for example, whether or not (S_n, T_n) is within the range of an actual camera image, or whether or not enlargement ratio or contraction ratio of the pixel is large or the like.

5

-Cylindrical model-

In the above-described road surface model, an object located above the horizon on a camera image is never on the plane of the road surface, even if the plane of the road surface is extended infinitely, so that the object cannot be viewed from the virtual point of view.

In order to reflect this object on the synthetic image from the virtual point of view, a cylindrical model as shown in Fig. 49 is used as a three-dimensional shape of the object. This model is advantageous, for example, when the direction of the virtual point of view is nearly parallel to the road surface.

For simplicity, a cylindrical model having its axes in the X-axis and the Z-axis is used. This model is represented by Equation (11) with (X_c, Z_c) as the center of an elliptic cylinder, using a parameter (a, c) of the ellipse. This also easily applies to models having their axes in the axes other than the X-axis and the Z-axis by rotation on the XZ plane.

$$\frac{(X_w - X_c)^2}{a^2} + \frac{(Z_w - Z_c)^2}{c^2} = 1 \quad (11)$$

The three-dimensional coordinates (X_w, Y_w, Z_w) of the

world coordinate system corresponding to the coordinates (S_v , T_v) of the synthetic image from the virtual point of view can be obtained by eliminating V_{ze} from Equation (5) using Equation (11). From these coordinates, as in the case of the
5 road surface plane model, the pixel corresponding to each camera image is calculated, so that the relationship between the pixel (S_v , T_v) of the image from the virtual point of view and the pixel (S_n , T_n) of the camera image is obtained and the mapping table is created.

10 Furthermore, a combination of the road surface plane model and the cylindrical model is possible. First, the three-dimensional coordinates of the world coordinate are obtained with the road surface plane model. When the three-dimensional coordinates are outside the cylindrical model, or
15 are not intersected with the plane, so that there is no solution, then the three-dimensional coordinates are obtained with the cylindrical model. Thus, synthesis can be performed in combination of the road surface plane model and the cylindrical model.

20 -Quasi-cylindrical model-

In order to facilitate grasp of the circumstances in distant places in the periphery of the road surface plane model, a bowl-shaped quasi-cylindrical model is introduced in
25 the periphery. Fig. 50 shows the shape of the model. The portion of a distant place is compressed for synthesis so that a wider range can be displayed. The shape of this

quasi-cylinder is represented by Equation (12).

$$\frac{(X_w - X_c)^2}{a^2} + \frac{(Y_w - Y_c)^2}{b^2} + \frac{(Z_w - Z_c)^2}{c^2} = 1 \quad (12)$$

The center of the bowl is (X_c, Y_c, Z_c) , and it has a
5 length of (a, b, c) in the X-axis, the Y-axis and the Z-axis
directions. As in the above cylindrical model, the three-
dimensional coordinates (X_w, Y_w, Z_w) of the world coordinate
system corresponding to the coordinates of the synthetic
10 relationship between each pixel of the synthetic image and
the pixel of each camera image can be obtained.

As in the case of the cylindrical model, a composite
model in a combination with the road surface plane model can
be used for synthesis.

15 -Processing for lens distortion correction-

Next, a method for correcting lens distortion by the
mapping table will be described. When there is distortion
due to lens distortion in actual camera images, the pixel
20 coordinates corrected with respect to this distortion are
calculated when an actual pixel (S_1, T_1) is obtained from U_v
and V_v as described above. Thus, the effect of lens
distortion can be removed from the synthetic image. This
distortion correction is incorporated into the relationship
25 between the synthetic image (S_v, T_v) of the mapping table and
the camera image (S_n, T_n) . Therefore, if the mapping table

corrected with respect to distortion is created first, at the actual synthesis, calculation for correction is not required. Also when distortion is not formalized, for example, in the case of the function of the distance from the lens center
5 that is used for conventional lens distortion correction, distortion correction can be achieved, provided that a pattern of lattice or the like is imaged and information on how each pixel moves because of lens distortion is obtained.

CLAIMS

1. An image processing apparatus comprising:

an image processing part for receiving images captured
5 by a plurality of cameras shooting surroundings of a vehicle
to generate a synthetic image viewed from a virtual point of
view from these camera images,

wherein the image processing part changes at least one
selected from a position, a direction of a line of sight, and
10 a focal length of the virtual point of view in accordance
with a running state of the vehicle.

2. The image processing apparatus of claim 1,

wherein the image processing part changes at least one
15 selected from a position, a direction of a line of sight, and
a focal length of the virtual point of view in accordance
with a running speed of the vehicle.

3. The image processing apparatus of claim 1,

20 wherein the image processing part changes at least one
selected from a position, a direction of a line of sight, and
a focal length of the virtual point of view, and controls
capturing of an image outside a view range of the changed
virtual point of view.

25

4. The image processing apparatus of claim 3,

wherein the image processing part controls the

capturing of an image outside a view range of the changed virtual point of view by changing a model for image synthesis.

5. The image processing apparatus of claim 1,

5 wherein the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal length of the virtual point of view in accordance with a steering angle of the vehicle.

10 6. The image processing apparatus of claim 1,

 wherein the vehicle includes an object detecting sensor for detecting an obstacle, and

 the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal
15 length of the virtual point of view in accordance with results of detection by the object detecting sensor.

7. The image processing apparatus of claim 1,

 wherein the image processing part includes an original
20 mapping table and generates a synthetic image using a mapping table that is cut out from the original mapping table, and

 the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal
length of the virtual point of view by changing the mapping
25 table to be cut out from the original mapping table.

8. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image viewed from a virtual point of view from these camera images,

5 wherein the image processing part controls capturing of an image outside a view range of the virtual point of view in accordance with a running state of the vehicle.

9. A monitoring system comprising:

10 a plurality of cameras shooting surroundings of a vehicle;

an image processing part for receiving images captured by the plurality of cameras to generate a synthetic image viewed from a virtual point of view from these camera images;

15 and

a display part for displaying the synthetic image,

wherein the image processing part changes at least one selected from a position, a direction of a line of sight, and a focal length of the virtual point of view in accordance
20 with a running state of the vehicle.

10. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle
25 to generate a synthetic image from these camera images,

wherein the image processing part generates an image including a first image and a second image as the synthetic

image,

the first image being viewed from the virtual point of view,

the second image being viewed from a viewpoint that is
5 different from the virtual point of view of the first image
in at least one selected from a position, a direction of a
line of sight and a focal length, or

the second image being different from the first image
in a model.

10

11. The image processing apparatus of claim 10,

wherein the second image is at least one of the camera
images.

15

12. The image processing apparatus of claim 10,

wherein the first image is a close view image showing
the vehicle and surroundings thereof, and

20

the second image is a distant view image showing an
area distant from the surrounding area of the vehicle that is
shown by the close view image.

13. The image processing apparatus of claim 12,

wherein the image processing part arranges the distant
view image around the close view image in the synthetic image.

25

14. The image processing apparatus of claim 13,

wherein the distant view image is an image having

continuity with the close view image.

15. The image processing apparatus of claim 10, wherein

the first image shows at least a part of the vehicle
5 and at least a part of the surroundings of the vehicle, and

the second image is obtained by enlarging at least a
part of the region shown by the first image.

16. A monitoring system comprising:

10 a plurality of cameras shooting surroundings of a
vehicle;

an image processing part for receiving images captured
by the plurality of cameras to generate a synthetic image
from these camera images; and

15 a display part for displaying the synthetic image,

wherein the image processing part generates an image
including a first image and a second image as the synthetic
image,

20 the first image being viewed from a virtual point of
view,

the second image being viewed from a viewpoint that is
different from the virtual point of view of the first image
in at least one selected from a position, a direction of a
line of sight and a focal length, or

25 the second image being different from the first image
in a model.

17. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images,

5 wherein in the synthetic image, the image processing part displays at least a part of a vehicle region where the vehicle is present, and an attention drawing region for drawing attention in which at least a part of the surroundings of the vehicle is shown.

10

18. The image processing apparatus of claim 17,

wherein the synthetic image is an image viewed from a virtual point of view that is set above the vehicle.

15 19. The image processing apparatus of claim 17,

wherein the image processing part displays an illustration image or an actual image of the vehicle on the vehicle region.

20 20. The image processing apparatus of claim 17,

wherein the attention drawing region includes at least a part of a blind spot region around the vehicle that is not shot by any of the cameras.

25 21. The image processing apparatus of claim 17,

wherein the attention drawing region corresponds to the blind spot region around the vehicle that is not shot by any

of the cameras.

22. The image processing apparatus of claim 20 or 21,

5 wherein the image processing part determines a range of
a region obtained by combining the blind spot region and the
vehicle region, using region data showing a projection region
of the vehicle in each camera image.

23. A monitoring system comprising:

10 a plurality of cameras shooting surroundings of a
vehicle;

an image processing part for receiving images captured
by the plurality of cameras to generate a synthetic image
from these camera images; and

15 a display part for displaying the synthetic image,
wherein in the synthetic image, the image processing
part displays at least a part of a vehicle region where the
vehicle is present, and an attention drawing region for
drawing attention in which at least a part of the
20 surroundings of the vehicle is shown.

24. An image processing apparatus comprising:

an image processing part for receiving images captured
by a plurality of cameras shooting surroundings of a vehicle
25 to generate a synthetic image from these camera images,

wherein the image processing part generates the
synthetic image, using a mapping table including first

mapping data describing a correspondence relationship between
pixels of the synthetic image and pixels of the camera images,
and second mapping data describing an identifier showing that
a pixel of the synthetic image corresponds to pixel data
5 other than the camera images.

25. The image processing apparatus of claim 24,
wherein the pixel data other than the camera images
show the vehicle or a blind spot region that is present in at
10 least a part of the surroundings of the vehicle.

26. The image processing apparatus of claim 24,
wherein the image processing part stores a
predetermined image other than the camera images, and
15 with respect to the pixel of the synthetic image, the
second mapping data describe coordinate values corresponding
to the pixel in the stored predetermined image.

27. The image processing apparatus of claim 24,
20 wherein the second mapping data describe pixel data
corresponding to the pixel of the synthetic image.

28. An image processing apparatus comprising:
an image processing part for receiving images captured
25 by a plurality of cameras shooting surroundings of a vehicle
to generate a synthetic image from these camera images,
wherein the image processing part uses mapping data

describing a correspondence relationship between pixels of the synthetic image and a plurality of pixel data including one or both of pixel data of the camera images and pixel data other than the camera images, and describing a rate of necessity with respect to each of the pixel data, and weights each pixel data in accordance with the rate of necessity,

thereby generating the pixel data of the pixels of the synthetic image.

10 29. An image processing apparatus comprising:

an image processing part for receiving images captured by a plurality of cameras shooting surroundings of a vehicle to generate a synthetic image from these camera images,


wherein the image processing part includes an original mapping table, cuts out a mapping table describing a correspondence relationship between pixels of the synthetic image and pixels of the camera images, and generates the synthetic image, using the cut-out mapping table.

ABSTRACT

A synthetic image viewed from a virtual point of view above a vehicle is generated, using images captured by a plurality of cameras shooting surroundings of the vehicle. In the synthetic image, an illustration image or an actual image of the vehicle is displayed in a vehicle region in which the vehicle is present. The area around the vehicle that is not shot by any of the cameras is displayed as a blind spot region.

1/47

FIG. 1



2/47

FIG. 2A






FIG. 2B




3/47

FIG. 3

Camera 1




Camera 3




Camera 2



Camera 5




Camera4



09/807654


4/47

FIG. 4



5/47

FIG. 5



09/807654-004300

6/47





FIG. 7



8/47

FIG. 8




FIG. 9





FIG. 10



11/47

FIG. 11

<MP15>


Camera number	X coordinate		Y coordinate		Rate of necessity
	R	G	B		
2	10		350		0. 2
99	0	0	255		0. 8

.....

09/ 807654

12/47

FIG. 12



13/47

FIG. 13






FIG. 14




14/47

FIG. 15




15/47

FIG. 16



Camera 4



Camera 0







FIG. 17

Camera 3




Camera 7




16/47

FIG . 18




17/47

FIG. 19A




Virtual point of view
height : 2.75m

FIG. 19B




Virtual point of view
height : 3m

FIG. 19C




Virtual point of view
height : 3.25m

FIG. 19D




Virtual point of view
height : 3.5m

FIG. 19E



Virtual point of view
height : 3.75m


FIG. 19F



Virtual point of view
height : 4m

Zoom-up
Zoom-down

FIG. 20A



Orientation: 22° backward
(Model: Road surface plane +
quasi-cylindrical surface)






FIG. 20B



Orientation: 17° backward
(Model: Road surface plane +
quasi-cylindrical surface)




FIG. 20C



Orientation: 11° backward
(Model: Road surface plane +
quasi-cylindrical surface)



FIG. 20D



Orientation:
straight downward
(Model : road surface plane)






FIG. 21A



Region occupied by an automobile when the automobile is moved.

Virtual point of view


FIG. 21B



Region occupied by an automobile when the automobile is moved.

20/47

FIG. 22A



Object detecting
sensor






FIG. 22B



21/47

FIG. 23


Region where an
obstacle is present



09/807654-0430



22/47

FIG. 24




Object detecting sensor

Virtual point of view :
Straight downward



Obstacle detection

Virtual point of view :
Straight downward



Virtual point of view :
To 11° backward





FIG. 25






FIG. 26C





FIG. 26D



25/47

FIG. 27B




FIG. 27C




FIG. 27D

FIG. 27E

FIG. 27F

FIG. 27G






FIG. 28



27/47


FIG . 29




28/47

FIG. 30

Camera 6



Camera 2



Downward view image from above





FIG. 30

29/47

FIG. 31

Downward view image in
a narrow range

Downward view image in
a wide range



09/807654-29/47

30/47

FIG. 32






FIG. 33



4466440" 44664400


32/47

FIG. 34



33/47


FIG . 35




09/807654

34/47




FIG. 36



35/47
FIG. 37



36/47




09/807654-0430

37/47


FIG. 39

Camera 6




A1

Camera 4



A2



38/47

FIG. 40






FIG. 41



40/47

FIG. 42



41/47

FIG. 43A


Correspond to PT4 (660, 290)



Mask data of Camera 2

FIG. 43B

Correspond to PT2 (150, 280)



Mask data of Camera 4

FIG. 43C

Correspond to PT2(480, 280)




Mask data of Camera 5

FIG. 43D

Correspond to PT1(450, 200)

Correspond to PT3(110, 250)



Mask data of Camera 6

FIG. 43A

42/47

FIG. 44A




FIG. 44B






FIG. 44C



43/47

FIG. 45



44/47

FIG. 46A




FIG. 46B

Attention
drawing region





FIG. 46C







FIG. 48



47/47

FIG. 49





FIG. 50



**Declaration and Power of Attorney for Patent Application
(English Language Declaration)**

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name,

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled

IMAGE PROCESSING APPARATUS AND MONITORING SYSTEM

the specification of which (check one)

☐ is attached hereto.

☒ was filed on **April 17, 2000** as United States Application No. or PCT International Application Number **PCT/JP00/02474** and was amended on _____ (if applicable).

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, Code of Federal Regulations, Section 1.56.

I hereby claim foreign priority benefits under Title 35, United States Code, Section 119(a) - (d) or Section 365(b) of any foreign application(s) for patent or inventor's certificate, or Section 365(a) of any PCT International application which designated at least one country other than the United States, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate or PCT International application having a filing date before that of the application on which priority is claimed.

Prior Foreign Application(s)

Priority Not Claimed

<u>11-109946</u> (Number)	<u>Japan</u> (Country)	<u>16/04/1999</u> (Day/Month/Year filed)
<u> </u> (Number)	<u> </u> (Country)	<u> </u> (Day/Month/Year filed)
<u> </u> (Number)	<u> </u> (Country)	<u> </u> (Day/Month/Year filed)

I hereby claim the benefit under 35 U.S.C. Section 119(e) of any United States provisional application(s) listed below:

(Application Serial Number)

(Filing Date)

(Application Serial Number)

(Filing Date)

(Application Serial Number)

(Filing Date)

I hereby claim the benefit under 35 U.S.C. Section 120 of any United States application(s), or Section 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of 35 U.S.C. Section 112, I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, C.F.R., Section 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application:

Application Serial No.

Filing Date

**Status – patented,
pending, abandoned**

_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

POWER OF ATTORNEY: As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark Office connected therewith. *(list name and registration number)*

Customer No. 27572
Harness, Dickey & Pierce, P.L.C.



Send Correspondence to:

Direct Telephone Calls to: *(name and telephone number)*

Gregory A. Stobbs, Esq. (248) 641-1214

Full name of sole or first inventor: Shusaku OKAMOTO

Inventor's signature: Shuaku OKAMOTO

Date: April 6, 2001

Residence: Osaka, Japan JPX

Citizenship: Japanese

Post Office Address: 3-6-10-215, Hoshigaoka, Hirakata-shi, Osaka 573-0013, Japan

Full name of second joint inventor, if any: Masamichi NAKAGAWA

Second Inventor's signature: Masanishi Nakagawa

Date: April 6, 2001

Residence: Osaka, Japan JDX

Citizenship: Japanese

Post Office Address: 22-5-304, Fujisaka-kitamachi, Hirakata-shi, Osaka 573-0151, Japan

3-00

Full name of third joint inventor, if any: Kunio NOBORI

Third Inventor's signature: Kunio Kobori

Date: April 6, 2001

Residence: Osaka, Japan JPX

Citizenship: Japanese

Post Office Address: 16-1-811, Joshoji-cho, Kadoma-shi, Osaka 571-0063, Japan

4.00

Full name of fourth joint inventor, if any: Atsushi MORIMURA

Fourth Inventor's signature: Atsushi Morimura

Date: April 6, 2001

Residence: Nara, Japan Jpx

Citizenship: Japanese

Post Office Address: 4-14-8, Nishitomigaoka, Nara-shi, Nara 631-0006, Japan

Full name of fifth joint inventor, if any: _____

Fifth Inventor's signature: _____

Date: _____

Residence: _____

Citizenship: _____